

#### FOR AUTHORIZED USE ONLY

# SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING & TECHNOLOGY,

VISHNUPURI, NANDED - 431 606

**Quotation Notice & Quotation** 

For

"Replacing flooring in Physics Dept of Admin Building"



## SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING & TECHNOLOGY, VISHNUPURI, NANDED-431 606.

**Date:-** 27/04/2022

#### SHORT NOTICE FOR CONTRACTORS

Sealed quotations are invited for <u>Replacing flooring in Physics Dept of Admin Building</u>. The prescribed format of this work is available our institute web site <a href="https://sggs.ac.in/tenders-site-section/">https://sggs.ac.in/tenders-site-section/</a>, from 28/04/2022 to 05/05/2022. The interested Govt. registered civil contractors/Agencies are requested to give their quotations for above mentioned work up to 05/05/2022 before 01.30 p.m. If possible, the quotations will be opened at 3.00 p.m. on the same day or next working day in the presence of contractor who will be remaining present.

The rights are reserved to accept or reject any or all quotation without any notice.

The contractors/Agencies should attach the following documents with Ouotation:-

- 1. The contractor/Agencies should attach with quotation the Registration copy of contractor with any of these Government Department PWD, CPWD, BSNL, MJP, MSSIDC and DIC. OR shop act.
- 2. Certificate of GST No.

In the absence of above any documents quotation stand cancelled.

Site Engineer

Secretary

Building & Construction Committee

Copy to the:

01 All Notice Boards in this Institute.

02 Concerned file No. 16

03 Institute web site.

Name of Contractor:	



### SHRI GURU GOBIND SINGHJI INSTITUTE OF ENGINEERING & TECHNOLOGY, VISHNUPURI, NANDED-431 606.

### QUOTATION

Name of the Work: - Replacing flooring in Physics Dept of Admin Building.

Item No.	Name of work	Qty.	Unit	Rate per Unit	Total Amount
Item No.1	Removing cement tiles, or marble or polished shahabad floor of dado without bed concrete including staking the materials as directed with all leads, lifts etc complete.	11.70	Sq.M.		
Item No.2	Providing & laying vitrified mirror/glossy finish tiles decorative type having size 590 mm to 605mm x 590mm to 605 mm of 8 to 10 mm thickness and confirming to IS.15622-2006 (group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc complete.	11.70	Sq.M.		
		Total .	Amount :-		

(Rate should be inclusive of GST)\*

(Inwards			

Place:-

Date:-

Sign. of Contractor/Agency with seal